BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Dasarahalli Division

D.T.S

Comprehensive Development works in Ward No 13. Shettyhalli Sub Division

S No	Item Name	Unit	Quantity	Rate In Figure in Rs	
				In Figures	in words
1	KSRRB 300-2. Earthwork excavation by manual means in Ordenary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (PWD SR 2018-19 P.No: 143, I.No.: 19.1)	Cum	22.98		
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications.MORTH -100/ Chapter 1 (PW,P& IWTD SR 2018-19, Pg No 16, Item No. 17.1 & 17	Cum	22.98		
3	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2(PW,P& IWTD SR 2018-19,Page No-13 Item No-4.2)	Cum	17.24		
4	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. - of size 450 x 200 x 400 mm (PWD SR 2018-19 P.No: 27, I.No.: 5.29.1)	No	1712.46		

5	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (PWD SR 2018-19 P.No: 180, I.No.:24.1)	Sqm	385.30		
6	Providing and fixing Executive bench made out of sadarahally grey stone with hand supporter with three line finishing with arch design, with 100mm slab height 90 X length 150 X width 45cms (data rate)	No	30.00		
7	For Eletrical & street lights	LS	1.00		

Number of corrections

Executive Engineer
Dasarahalli Division

DTS Approved

ಅಂದಿಕೆ: ಇದ್ದು ಸಾದರಪಡಿಸುವ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು(ವಿ.ವಿ.....)ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಪರತ್ತಿಗೆ ಒಳಪಡಿಸಿ ಡಿ.ಟಿ.ಎಸ್
ಅನುಮೋದಿಸಿದೆ.
ಕರದು ಟೆಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ.
ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ: Null.....
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಪುಟಗಳ ಸಂಖ್ಯೆ...Null.....
ಮುಖ್ಯ ಅಭಿಯಂತರರು (ದಾಸರಹಳ್ಳಿ)